AdonisBIMsolutions

Mahindra - Eminente



Adonis Designs

- BIM Model coordinated with SMEP
- •CCD Revit & Navisworks
- BIM model embedded with all SMEP drawings
- Value Additions
- Emergent BIM areas

Overviewofwork

- Design Interpretation
- Coordination

2D

3D

4D

- BIM-Arch. Production
- BIM-MEP Coordination
- Clash Detection
- Constructability Issues /Value Additions
- 4D Sampling
- Facilities Mgmt.

Design Interpretation

Coordination

2D





- BIM-MEP Coordination
- Clash Detection



3D



BIMisVE



Evaluation hi5 FCR

Types of Analytic Checks:

- Regulatory/Bylaws
- Coordination-External
- Coordination-Internal
- •On Hold
- Design
- Incomplete Information
- Manufacturer/Contractor

Evaluation hi5 FCR

ADONIS DESIGNS

Mahindra Eminente Aspen : Clash Control and Detection Report

Eminente - Hi5 Clash Control Detections

S.No	Туре	Owner	Problem	Value	VE Category	Resolution
1	Regulatory By Laws – Fire Safety	Architecture, Plumbing, Mechanical	Refuge Detail Design ,Egress Staircase, Fire escape route, Signage's, Smoke stop door, FHC, Wall fire Rating etc	High	First Cost Reduction	Compliance Check to be done Life safety drawings for Egress Staircase, Escape Routes, Refuge Floor to be developed to avoid objections from regulatory authority and site approval delays
2	Design	Plumbing,	Rainwater Collection/Harvesting not shown, OHT pipe connection not shown	High	First Cost Reduction	Design check list or switch to BIM platform
3	Coordination External	Structure, Architecture Plumbing	Beam conditions, Unsupported Walls, Slab Conditions Service Cutouts	High	First Cost Reduction	Improve Coordination and introduce Interdiscipline CCD meetings and CCD drawing ,Refer to Hi 5 Drawing Set
4	Coordination Internal	Structure, Architecture	Beam conditions, Beam Naming, Parapet Sizes Door Window Numbering and Schedule Missing Information	High	First Cost Reduction	Improvisation of Internal sheet wise Coordination amongst individual discipline, Refer to Hi 5 Drawing Set
5	Incomplete Information , On Hold	All discipline	Basement & Stilt stairs Open ended information, Non Connected pipes, On Hold areas, Electrical Cable Routing	High	First Cost Reduction	All the drawing details to be completed and indpendently checked by an Audit Team or Virtual Construction Team before sending to site or use the power of BIM, Refer to Hi 5 Drawing Set

Evaluation hi1 FCR



Evaluation hi2 FCR



Evaluation hi3 FCR



Evaluation hi4 FCR



Evaluation hi5 FCR



Evaluation hi5 FCR

Mahindra Eminente Aspen : Clash Control and Detection Report

					VALUE		TOTAL			
S.NO.	LEVEL	OWNER	SUB OWNER	ТҮРЕ	CATEGORY	INSTANCES	COUNT	DESCRIPTION	REFRAL DOCUMENT	
1	UGR							ОК		
2	BASEMENT							ОК		
3	STILT	Architecture	Architecture	Coordination-Internal	High	1		Levels are not matching	Y:\Mahindra\Working\Clarifica tions\Final clarifications\1_Arch to Arch\Stilt\3	
		Architcture	Architcture	Incomplete Information	High	1	1	Stair with incomplete information	Y:\Mahindra\Working\Clarifica tions\Final clarifications\1_Arch to Arch\Stilt\1	
		Architcture	Architcture	Regulatory/Bylaws	High	1	1	fire escape routing/signage not defined	Y:\Mahindra\Working\Clarifica tions\Final clarifications\1_Arch to Arch\Stilt\2	
4	PODIUM	Architcture	Architcture	Incomplete Information	High	1X2 = 2	2	Stairs with incomplete information	Y:\Mahindra\Working\Clarifica tions\Final clarifications\1_Arch to Arch\Podium	
		Architcture	Architcture	Coordination-Internal	Medium	1X12 = 12(x5)	12	Parapet wall @ service slab.		
5	FLOOR (TYP. 1st to 5th)	Architcture	Architcture	Regulatory/Bylaws	High	1X3	1	Core area (egress, lift, electrical service shaft, refuge area)	Y-\Mahindra\Working\Clarifica	
	ſ	Architcture	Architcture	Coordination-Internal	High	1(x23)	1	Annotation, window schedule error.	tions) Final	
6	FLOOR (TYP. 6th to 10th)	Architcture	Architcture	Coordination-Internal	Medium	1X12 = 12(x5)	12	Parapet wall @ service slab.	clarifications 1 Arch to	
7	FLOOR (TYP. 11th to 15th)	Architcture	Architcture	Coordination-Internal	Medium	1X12 = 12(x5)	12	Parapet wall @ service slab.	Arch\Typical floor\1	
8	FLOOR (TYP. 16th to 20th)	Architcture	Architcture	Coordination-Internal	Medium	1X12 = 12(x5)	12	Parapet wall @ service slab.		
9	FLOOR (TYP. 21st & 22nd)	Architcture	Architcture	Coordination-Internal	Medium	1X12 = 12(x2)	12	Parapet wall @ service slab.		
10	23rd	Architcture	Architcture	Coordination-Internal	Medium	1X12 = 12	12	Parapet wall @ service slab.	1	
11	24th	Architcture	Architcture	Coordination-Internal	High	1	1	Balcony mismach @ grid 9.	Y:\Mahindra\Working\Clarifica tions\Final	
12	TERRACE									
13	LMR & OHT									
14	TOP ROOF									
						Sum of Counts	75			

Cost Factor	5500						
RESULTS							
Category	Total Counts	Value	Cost				
Low	0	Upto 2hrs	0				
Medium	73	Upto 4Hrs	1606000				
High	7	Above 6hrs	231000				
Total Value On Site		1837000					

ADONIS DESIGNS

Evaluation hi5 FCR Cost Vs Time



BIM VE final evaluation

Total Costructability Issues



BIM VEclimbing the ladder





Emergent categories of BIM evolution

- 1. Visualization Sectional Perspectives, Renderings
- 2. Production Schedules, Area Calculations, Annotation
- 3. Coordination Interference Detection, 3D from consultants
- 4. Analysis Structural, Thermal, Egress
- 5. Supply Chain Integration 4D Simulation, CNC Fabrication, FM, Intelligent Site

BIM VE images



BIM VE images



BIM VE images



Adonis Eminente Team

Ishtiaq Masoodi Director Production

Project Profile: Production Supervision, Technical Support Production Team Members: Kashif Khan, Amarpal Kaur

M Keshav Project Architect/BIM Specialist B Arch

Project Profile: BIM & MEP Support , Visualization, 3D services

Pritpal Singh Project Architect/Sustainability Specialist MCIAT,ICBC AP, BBA

Project Profile: Tech Support , Navis Works –CCD, Value additions,4D services

Adonis Green Thanks

